



BUILDING QUOTATION

A residence at Hamilton Hill

Prepared for the construction of a new two-storey custom residence, including basement garage, pool and landscaping.

PREPARED FOR

Mr & Mrs J. Whitmore
0400 000 000
j.whitmore@example.com

QUOTE REFERENCE

LUX-2026-0148
Issued 12 August 2026
Valid for 30 days

PROJECT ADDRESS

14 Kingsford Smith Drive
Hamilton QLD 4007
Lot 8 · SP 214 556

TOTAL INVESTMENT

\$1,850,000
Including GST

SECTION 01

Construction stages & progress payments

Payments are claimed at the completion of each stage below and are due within five business days of the claim being issued. Percentages follow the QBCC Level 2 Housing Contract schedule.

STAGE	SCOPE OF WORKS	%	AMOUNT
1 Deposit	Contract signing, engineering, soil test, council and certifier lodgement	5%	\$92,500
2 Base	Site cut, piling, basement retaining, waffle raft slab poured and cured	15%	\$277,500
3 Frame	Structural steel, wall and roof framing complete and frame inspection passed	20%	\$370,000
4 Enclosed	Roof cover, external cladding, windows and external doors installed	20%	\$370,000
5 Fixing	Linings, joinery, stone, tiling, internal doors, skirtings and architraves	20%	\$370,000
6 Practical completion	Pool, landscaping, driveway, final clean, handover and warranty documents	20%	\$370,000

Contract sum (excl. GST)\$1,681,818.18

GST 10%\$168,181.82

TOTAL INCL. GST**\$1,850,000**

SECTION 02

What each stage includes

Everything listed below is allowed for within the contract sum. Where an allowance is stated, the figure is a supply-and-install budget confirmed at selections.

1

Deposit

\$92,500

5% OF CONTRACT

1.1 · DESIGN & DOCUMENTATION

- Full working drawings, engineering and energy efficiency report
- Soil test and contour survey by a registered surveyor
- Building approval lodgement with a private certifier

1.2 · APPROVALS & INSURANCES

- QBCC Home Warranty Insurance and contract works cover
- Council infrastructure charges and plumbing application fees
- Site establishment: temporary fencing, amenities and site power

2**Base****\$277,500**

15% OF CONTRACT

2.1 · FOUNDATIONS

- Engineer-designed waffle raft slab to AS 2870, class M soil classification
- Bored concrete piers to basement retaining walls, depths per geotechnical report
- Termite management system to AS 3660 with 50-year product warranty

2.2 · EARTHWORKS & DRAINAGE

- Site cut and benching to engineer's levels, spoil removed from site
- Stormwater drainage to legal point of discharge with silt control
- Under-slab plumbing rough-in and service conduits

3**Frame****\$370,000**

20% OF CONTRACT

3.1 · STRUCTURAL FRAME

- Structural steel beams and columns, hot-dip galvanised, primed and certified
- MGP10 seasoned pine wall frames at 450mm centres, 2740mm ceiling height
- Engineered roof trusses, wind rated to N3 with cyclone tie-down straps

3.2 · SERVICES ROUGH-IN

- Electrical rough-in including Cat6 data cabling to eight locations
- Ducted air conditioning rough-in, four zones with dedicated returns
- Hydronic and gas rough-in to kitchen, laundry and outdoor kitchen

4**Enclosed****\$370,000**

20% OF CONTRACT

4.1 · ROOF & EXTERNAL CLADDING

- Colorbond Ultra standing seam roof with concealed box gutters
- Rendered blockwork to ground floor, acrylic texture coat in three-colour scheme
- Sarking, wall wrap and R2.5 external wall insulation throughout

4.2 · GLAZING & EXTERNAL DOORS

- Commercial-grade thermally broken aluminium glazing, double glazed throughout
- Pivot entry door in solid American oak, 1200 x 2700mm with concealed hardware
- Stacking sliding doors to alfresco with flush sill detail

5**Fixing****\$370,000**

20% OF CONTRACT

5.1 · SKIRTING & INTERNAL DETAILING

- 185mm square-set MDF skirting, glued and set flush with two-pack finish
- Shadowline ceiling detail to living, dining and primary suite
- Concealed door jambs to all internal doors, 2340mm height

5.2 · KITCHEN & WET AREAS

- Custom two-pack joinery with 20mm engineered stone tops and waterfall ends
- Appliance allowance of \$28,000 including integrated refrigeration
- Full-height tiling to all bathrooms, tile allowance \$95/m² supply

5.3 · ELECTRICAL & SUSTAINABLE ENERGY

- 10kW solar array with 13.5kWh battery storage and hybrid inverter
- Recessed LED downlights on dimmable circuits, allowance of 64 fittings
- EV charger rough-in to basement garage, 32A single phase

6

Practical completion

\$370,000

20% OF CONTRACT

6.1 · POOL & OUTDOOR LIVING

- 10m concrete lap pool, fully tiled with glass mosaic waterline and gas heating
- Outdoor kitchen with teppanyaki plate, sink and integrated bar refrigeration
- Pool fencing, paving and turf to rear yard

6.2 · LANDSCAPING & DRIVEWAY

- Exposed aggregate driveway with automated sliding gate and intercom
- Landscape package to approved plan including irrigation to garden beds

6.3 · HANDOVER

- Final builder's clean, window clean and pest treatment
- Handover walkthrough, keys, warranty folder and maintenance schedule

SECTION 03

Disclaimer

This quotation is an estimate based on the drawings, specifications and site information available at the date of issue. It is not a fixed-price building contract.

Prices are subject to final engineering, soil classification, service connection points and council or private certifier conditions. Any variation to these will be priced as a written variation before works proceed.

Allowances noted throughout are budget figures for supply and install. Where selections exceed an allowance, the difference is charged at cost plus the builder's margin stated in the contract.

Rock excavation, contaminated soil, asbestos removal, retaining to neighbouring boundaries and latent site conditions are excluded unless expressly listed as an inclusion.

SECTION 04

Terms & conditions

1 · Validity & acceptance

- This quotation remains open for acceptance for 30 days from the date of issue.
- Acceptance occurs on execution of a QBCC Level 2 Housing Contract, not on signing this document.
- Supplier pricing held for 30 days only; beyond that, material rates are reconfirmed before contract.

2 · Payments

- Progress claims are issued at completion of each stage and are payable within five business days.
- Overdue amounts accrue interest at 10% per annum, calculated daily.
- The builder may suspend works while a claim remains unpaid; resulting delay costs are borne by the client.

3 · Variations

- All variations are documented, priced and signed by both parties before the work is carried out.
- Variations are invoiced at the next progress claim unless otherwise agreed in writing.
- Client-requested changes after a stage has commenced may attract a rework charge at cost.

4 · Program & site access

- Indicative build program is 62 weeks from slab pour, subject to weather and approvals.
- Extensions of time apply for inclement weather, industry shutdowns and supply delays outside the builder's control.
- Site visits are by appointment only, accompanied by the site supervisor, for insurance reasons.

5 · Insurance & warranties

- QBCC Home Warranty Insurance and \$20m public liability cover are held for the duration of works.
- Contract works insurance covers the structure until handover; client contents are excluded.
- Defect liability period of 12 months from practical completion; manufacturer warranties pass to the client.

6 · Selections & allowances

- Final selections are to be confirmed at the colour appointment within 21 days of contract signing.
- Late selections that delay ordering may extend the program and attract holding costs.
- Natural stone, timber and handmade tiles vary in colour and grain; variation is not a defect.

SECTION 05

Acknowledgement

By signing below, the client confirms they have read the stages, inclusions, disclaimer and terms set out in this quotation, and that the scope described reflects the home they wish to build.

CLIENT 1 FULL NAME

CLIENT 2 FULL NAME

POSTAL ADDRESS

EMAIL

CONTACT NUMBER

PROJECT ADDRESS

CLIENT SIGNATURE

FOR LUXURIA HOMES

Signed

Date

Signed

Date

Return the signed pages to build@luxuriahomes.com.au and we will prepare your contract documents.

Luxuria Homes